## SENTRIGARD ML 100AH, 16" WIDE LOAD TABLE OVER 15/32" PLYWOOD



Buildings having a Roof Mean Height≤ 20'-0"; Roof Slope: 2"/12" -6"/12" Gable or Hip Roof Wind Speeds 130-170 mph, Exp C, Risk Category II, Enclosed Bldg. based on FLORIDA BUILDING CODE 2010

SENTRIGARD ML 100AH, 16" WIDE, CLIP SPACING							
	FASTENER	SUBSTRATE	WIND SPEED ZONE				
ZONE			130	140	150	160	170
			ON CENTER SPACING	ON CENTER SPACING	ON CENTER SPACING	ON CENTER SPACING	ON CENTER SPACING
ZONE 1	(2) #12-11 x 1"	15/32" CDX PLYWOOD	24"	24"	24"	24"	24"
ZONE 2	(2) #12-11 x 1"	15/32" CDX PLYWOOD	24"	24"	24"	6"	6"
ZONE 3	(2) #12-11 x 1"	15/32" CDX PLYWOOD	6"	6"	6"	6"	6"

- 1) PANEL DESCRIPTION: 1" MECHANICAL LOCK, MIN. 0.032" ALUM., 16" MAX WIDTH, DOUBLE LOCK SEAM.
- 2) PANEL FASTENER: (2) #12-11 x 1" TYPE A PANCAKE HEAD PER CLIP.
- 3) PANEL CLIP: UC3 STAINLESS STEEL FLOATING CLIP
- 4) MAXIMUM ALLOWABLE PANEL UPLIFT PRESSURE: 63.5 PSF @ 24" O.C., 101.0 PSF @ 6" O.C. PRESSURE BASED ON UL 580/UL 1897 TESTING BY FORCE ENGINEERING TEST REPORT #72-0191T-07A-C.
- 5) PLYWOOD DECKING: MIN. 15/32" THICK, APA RATED PLYWOODD. MUST BE DESIGNED IN ACCORDANCE WITH FBC 2010.
- 6) PANEL ROLLFORMER: SCHLEBACH QUADRO-PLUS ROLLFORMER BY METALFORMING, INC.
- 7) LOAD TABLE BASED ON WIND PRESSURES CALCULATED PER ASCE 7-10 (Kd=0.85) MULTIPLIED BY 0.6 PER FBC 2010, SECTION 1609.1.5.
- 8) LOAD TABLE DOES NOT INCLUDE OVERHANG ZONES

